


TREATMENT OF ACID MINE DRAINAGE IN HUFF RUN, SUNDAY, MONDAY, LEADING AND RACCOON CREEK WATERSHEDS, OHIO

BEN McCAMENT

OHIO DEPARTMENT OF NATURAL RESOURCES
DIVISION OF MINERAL RESOURCES MANAGEMENT
AML PROGRAM















AMDAT

Watershed Identification

Extent AMD Impacts


Source Characterization

Project ID



Cost / Benefit

Funding Sources


Monitoring Plan






Map Legend


-  AMDAT Watersheds
-  Surface Mines
-  Underground Mines
-  Ohio Counties





Watersheds Surveyed	AMD Present	AMD Absent
134	83	51

-  Ohio Counties
- 12 HUC Watersheds**
-  AMD Absent
-  AMD Present





Inset 2

Partnerships

- Ohio Dept. of Natural Resources
- Ohio EPA
- US Office of Surface Mining
- Wayne National Forest
- Muskingum Watershed Conservancy District
- Local Soil and Water Conservation Districts
- Ohio University – Voinovich School
- Rural Action
- Watershed Groups
- Coal Industry
- US Army Corps of Engineers



Watershed	Total number of completed projects	Total costs
Raccoon Creek	20	\$14,521,361
Monday Creek	18 (plus 5 subsidence projects, costs are not included)	\$7,197,808
Sunday Creek	12 (7 of 10 are subsidence projects)	\$2,618,273
Huff Run	14	\$5,308,353
Leading Creek	2	\$728,481
Total	66	\$30,374,277



11/18/2011









7 10:43 AM



08/13/2012



Flint Run East and Lake Milton AMD Treatment Systems

Upper Lake Milton

FR0130

Vertical flow pond (FR0190)

Lake Milton

FR0122

SSLB

FR0180

OLC

Sediment pond (FR0152)

Vertical flow pond (FR0150)

Wetland ditch

Horizontal LLB (FR0148)

Storage pond for treated water

SSLB (FR0144)

FR0126

FR0140

FR0120

FR0170

coal drainage

water discharge

sediment pond (Hothouse Lake)





Table 1: Types of AMD Treatment Systems in Use in Ohio

	Passive Treatment							Active Treatment	Source Control	
Type of System	SLB	LLB	Wetland	VFP/SAPS	OLC	ALD	Bioreactor	Lime Doser	Reclamation	Stream Capture
# of systems	15	10	9	3	3	1	1	6	16	12

2016 STREAM HEALTH REPORT

AN EVALUATION OF WATER QUALITY, BIOLOGY, AND ACID MINE DRAINAGE RECLAMATION IN FIVE WATERSHEDS: RACCOON CREEK, MONDAY CREEK, SUNDAY CREEK, HUFF RUN, AND LEADING CREEK.



CREATED BY:

VOINOVICH SCHOOL OF LEADERSHIP AND PUBLIC AFFAIRS
AT OHIO UNIVERSITY

JENNIFER BOWMAN, NORA SULLIVAN, AND KELLY JOHNSON

6-30-2017



78.5%



Watershed	Total number of completed projects	Total costs	Total acid load reduction lbs/day	Total stream miles improved in 2005/2010/2016 to meet IBI & MAIS Biological stream health targets	Stream miles that met the pH target	Total stream miles monitored
Raccoon Creek	20	\$14,521,361	4,267	23.3/18.4/40.3 (82.0)	110	117
Monday Creek	18 (plus 5 subsidence projects, costs are not included)	\$7,197,808	4,360	0/0	23	32
Sunday Creek	12 (7 of 10 are subsidence projects)	\$2,618,273	22	0/5.3/6.2 (11.5)	43	43
Huff Run	14	\$5,308,353	1,129	0/0	8	10
Leading Creek	2	\$728,481	663	NA/0	9	9
Total	66	\$30,374,277	10,441	23.3/23.7/46.5 (93.5)	193	211

Reductions


Total to date acid load reductions = 10,441 lbs/day

Costs


Total to date reclamation costs = \$30,374,277

Lake Milton site FR0120

Lake Milton site FR0120 Yearly Acid Load Reduction




Lake Milton site FR0120 Yearly Metal Load Reduction




East Branch Phase I site EB210


East Branch Phase I site EB210 Yearly Acid Load Reduction




East Branch Phase I site EB210 Yearly Metal Load Reduction




Raccoon Creek Headwaters Mainstem pH




West Branch Sunday Creek Mainstem pH



Monday Creek Headwaters Mainstem pH




Huff Run Mainstem pH



RACCOON CREEK HEADWATERS

Average Net Alkalinity



WEST BRANCH SUNDAY CREEK

Average Aluminum

—▲— 2016

—◆— 2005

— Al target








Figure 1: Biological health Improvements In Raccoon Creek from baseline (1997) to 2015.







Figure 2: Biological health Improvement In Sunday Creek West Branch from 2005 to 2015.




Monday Creek




Monday Creek

Baseline: 2000 - 2003


2010 - 2015




MONDAY CREEK FISH DATA



Raccoon Creek



Little Raccoon Creek



LITTLE RACCOON CREEK

Baseline: ~ 2000 - 2005

2014 - 2015





Figure 6: Little Raccoon Creek fish Community Recovery 1980s, 1990s, and 2000s.



AMD PROJECT COST & RECOVERY ANALYSIS

Categories	Leading Creek	Sunday Creek	Raccoon Creek	Huff Run	Monday Creek	Total	Average
No. of Projects	2	12	20	14	18	66	
Project Costs	\$728,481	\$2,618,273	\$14,521,361	\$5,308,353	\$7,197,808	\$30,374,276	
Acid Load Reduction (lbs/day)	661.00	352.00	4,267.00	1,129.00	4,360.00		2,153.80
Cost per lb of acid removed	\$1,102	\$7,438	\$3,403	\$4,702	\$1,651		\$3,659
Miles Improved*	7			6	21	34	
Miles Recovered	0	11.5	82	0	0	93.5	
Cost per mile improved	\$104,069	NA	NA	\$884,726	\$342,753	NA	\$443,849
Cost per mile recovered	NA	\$227,676	\$177,090	NA	NA	NA	\$202,383
Cost per foot improved	\$20	NA	NA	\$144	\$195	NA	\$119
Cost per foot recovered	NA	\$43	\$34	NA	NA	NA	\$38

** miles improved is estimated*

CHALLENGES

- **DETERMINING SUCCESS AND WHEN STREAM HAS REACHED POTENTIAL SHORT TERM RECOVERY**
- **TAKES YEARS OR DECADES TO SEE RESULTS IN SOME CASES. PRESSURE FOR IMMEDIATE RESULTS.**
- **LONG TERM O&M FUNDING**
- **DIFFICULT TO LEVERAGE “OTHER” SOURCES OF FUNDING FOR O&M PROJECTS**
- **OTHER NPS ISSUES MAY NEED TO BE ADDRESSED TO ACHIEVE FULL POTENTIAL RECOVERY. NEED MULTI-AGENCY FUNDING & SUPPORT.**
- **USING AMD FUNDS TO ASSIST WITH WATERSHED MANAGEMENT FOR “HOLISTIC” RESTORATION WORK**



Long Term Operation and Maintenance of Acid Mine Drainage Treatment Projects



March 29, 2017

Table 1. Results of AMD Project Operation and Maintenance Prioritization

Priority 1	Priority 2	Priority 3	Scheduled to be Abandoned at end of life cycle	Total # of Projects Prioritized
23	9	6	8	46

Table 2. Results of 30-Year O&M Cost Estimate Analysis for Priority AMD Projects

Total Cost Priority 1	Total Cost Priority 2	Total Cost Priority 3	Total Cost All priority projects	Average annual cost all priority projects	Average annual cost priority 1 projects only
\$15,810,749	\$2,553,033	\$1,160,373	\$19,524,155	\$650,805	\$527,025



Questions?



Benny.Mccament@dnr.state.oh.us

740-274-4947