

Banning No. 4 Mine: A Tale of Title V Facility Retrofit Project Development

Sami Pretzel, Brian Osborn, Dingfang Liu




Outline

- Introduction
- Mine Pool Hydrology
- ATP Design
- Project Milestones

Introduction

- ❑ Two aged ATPs
 - Banning
 - H₂O₂ + Polymer → Clarifier
 - Euclid
- ❑ Maintain mine pool elevation to prevent flooding
- ❑ Meet WQ objectives:
 - Total Fe < 1.5 mg/L
 - TSS < 35 mg/L





Mine Drainage Water Quality

Parameter	Unit	Banning	Euclid	Estimated Mix	Design Parameters
Quantity	MLD	15.26	21.80		35.38
pH	SU	7.3	7.1	~7.17	
Specific Cond.	uS/cm	2,700	2,730		
TDS	mg/l	1,850	1,956	1,912	
TSS	mg/l	20*	28	25	35
Field Alkalinity	mg/l	512	410	452	
Lab Alkalinity	mg/l	538	388	450	
Hot Acidity	mg/l	-509	-361	-422	
Total Aluminum	mg/l	0.30*	0.30*	0.30	
Dissolved Aluminum	mg/l	0.30*	0.30*	0.30	
Total Iron	mg/l	10.24	30.00	21.86	1.5
Dissolved Iron	mg/l	8.62	23.20	17.19	
Total Manganese	mg/l	0.29	0.64	0.49	
Dissolved Manganese	mg/l	0.27	0.62	0.47	
Sulfate	mg/l	811	1,025	937	

* Detection limits


Mine Pool

- ❑ Determination of combined plant capacity 35.38 MLD (6,500 gpm)
 - Flow metering @ ATPs
 - Analysis of mine pool elev. 225.5 m (MSL)
- ❑ Vertical Turbine Pump (VTP)
 - borehole locations
- ❑ Sludge flow assessment



Banning No.4 Mine Pool
ation Title Area)

Process Flow Diagram



Site Overview

Outlet to River (Main Disposal)


Provision for Future Expansion

Raised Grade to above 100-yr Flood Elev.

Proposed Wetland as Alt. Effl. Refinement

Mine Void Pumps (Vertical Turbine)

Wetland Outlet to River



Plant Layout

- Two clarifiers 112 ft diameter
 - maximum design flow of 6,500 GPM.
 - surface loading rate of 0.75 GPM/SF

Clarifiers (2)

Recirculation
Pump (4)

Polymer System


Wasting
Pump (2)

Flocculation
Tanks (2)



Reaction Tanks
(2)

Mixing/Aeration &
Flow Split (1)

Operations
Building



Reaction Tank Operational Options




Recirculation Pump Room

High Flow
Recirculation
Pumps (2)

Low Flow
Recirculation
Pumps (2)

Wasting
Pumps (2)



Project Milestones

- 30% Design finished on Jan 2024
- 75% Design Scheduled for September 2024
- 100% Design Scheduled for January 2025
- Bid Ready Documents scheduled for March 2025

Acknowledgement

OSM

Brent Means

Richard Beam

PA DEP

Dan Koury

Clean Stream Foundation

Jypsee Hedrick

Don Charlton

Kleinfelder Project Team

Sami Pretzel

Brian Osborn

Jose Infante-Corona

Shugen Pan

Tom Clark